



Florida Department of Environmental Protection

Marjory Stoneman Douglas Building
3900 Commonwealth Boulevard
Tallahassee, Florida 32399-3000

Rick Scott
Governor

Jennifer Carroll
Lt. Governor

Herschel T. Vinyard Jr.
Secretary

CERTIFIED - RETURN RECEIPT REQUESTED

November 14, 2012

U.S. Army Corps of Engineers
Attn.: Eric Summa
P.O. Box 4970
Jacksonville, Florida 32232-0019

Permit Modification No. 0308009-003-JN
Permit No. 0308009-001-JC, Volusia County
Ponce de Leon Inlet Maintenance Dredging, Minor Modification

Dear Mr. Summa:

Your request to modify Permit No. 0308009-001-JC was received on August 17, 2012, and has been reviewed by Department staff. The proposed permit modification is to revise the language of Specific Condition (SC) 1 to be consistent with the Interagency Coordination Agreement for Civil Works Projects (2006); revise the language of SC 7 to adhere to the recommendations of the Florida Fish & Wildlife Conservation Commission (FWC); and to correct the project name and permit number in the document 'header' of the Final Order on pages 3, 5, 7, 9, 11, 13, and 15. The changes to SCs 1 and 7 are discussed below. The change to the document header has been made separately, as an administrative correction (see attached permit).

Permit History

On September 12, 2011, the U.S. Army Corps of Engineers (Corps) applied for a Joint Coastal Permit to dredge material from Ponce de Leon Inlet access channel, Inlet throat, and north and south navigation channels be deposited in a nearshore disposal area, located 1 mile south of the Inlet. Permit No. **0308009-001-JC** authorizes the Corps to place the dredged material in the nearshore site one time only. Beach-quality material dredged during subsequent events was to be placed on the beach. However, a permit modification would be required for any future placement.

On August 8, 2012, the Corps requested a modification to Permit No. 0308009-001-JC to remove the one-time-only restriction on nearshore placement, allow near beach-quality material to be placed in the nearshore disposal site, and add a contingency allowing additional nearshore disposal events if beach-quality material is not available or if economic constraints mandate nearshore disposal. The application for Modification No. **0308009-002-JN** was withdrawn on August 15, 2012.

Notice of Permit Modification
Permit Modification No. 0308009-003-JN
Ponce de Leon Inlet Maintenance Dredging
Page 2 of 9

For additional background regarding activities related to the project area, please see the Consolidated Notice of Intent to Issue Joint Coastal Permit, and Authorization to Use Sovereign Submerged Lands for Permit No. 0308009-001-JC at the following website:

http://bcs.dep.state.fl.us/env-prmt/volusia/issued/0308009_Ponce_de_Leon_Inlet_Maintenance_Dredging/001-JC/Intent%20to%20Issue/071012%20Intent%20to%20Issue.pdf

Modification Justification

The project description in the original permit is not consistent with the language contained in the Interagency Coordination Agreement for Civil Works Projects (ICA) of 2006 between the Department and the Corps. The modification to SC 1 will make the project description consistent with the ICA.

The proposed modification of SC 7 is necessary to make the permit conditions consistent with the recommended permit conditions from the FWC. The initial FWC comments provided to the Department were not definitive regarding turbidity barrier composition, included examples of signs that are now recommended for viewing on the FWC website, and contained more stringent restrictions regarding operations than are warranted by the project. The FWC provided the recommended revision to SC 7 to correct these inconsistencies, as shown below.

Staff Assessment

The Permittee has provided the Department with reasonable assurance that the proposed modifications will not cause adverse ecological impact or decrease the protection of the resource.

The proposed modifications of SCs 1 and 7 make the permit consistent with the ICA and permit conditions recommended by the FWC, respectively. The proposed permit modification does not change the scope of the proposed activity; therefore, the modification is not anticipated to adversely impact water quality or the environment.

The specific conditions shall be revised as follows (~~strikethroughs~~ are deletions, underlines are additions):

SPECIFIC CONDITIONS:

1. The Permittee and the Department, within their respective authorities and funding, shall ensure that beach compatible dredged material is placed on Florida's beaches, consistent with Florida's beach management plan adopted pursuant to Chapter 161, F.S. and other beneficial uses criteria as may be specified by the Department and applicable federal standards. The authorized activity includes a one-time placement of dredged beach-quality material in the nearshore disposal area. Future maintenance dredging events will be required to place beach-quality dredged material on the beach per the Ponce de Leon


Notice of Permit Modification
Permit Modification No. 0308009-003-JN
Ponce de Leon Inlet Maintenance Dredging
Page 3 of 9

Inlet Management Plan of 1997 to the maximum extent practicable when sufficient beach-quality material and funding are available. If the Permittee desires to perform additional maintenance dredging events under this authorization, a permit modification will be necessary.

7. **Manatee and Marine Turtle Protection Conditions:** During all construction authorized by this permit, the Permittee shall comply with the following conditions intended to protect manatees and marine turtles from direct project effects:
- a. All personnel associated with the project shall be instructed about the presence of marine turtles, manatees and manatee speed zones, and the need to avoid collisions with (and injury to) these protected marine species. The Permittee shall advise all construction personnel that there are civil and criminal penalties for harming, harassing, or killing manatees which are protected under the Marine Mammal Protection Act, the Endangered Species Act, and the Florida Manatee Sanctuary Act.
 - b. All vessels associated with the construction project shall operate at "Idle Speed/No Wake" at all times while in the immediate area and while in water where the draft of the vessel provides less than a four-foot clearance from the bottom. All vessels will follow routes of deep water whenever possible.
 - c. ~~If siltation or turbidity barriers are used,~~ they shall be made of material in which manatees and marine turtles cannot become entangled, shall be properly secured, and shall be regularly monitored to avoid entanglement or entrapment. Barriers must not impede manatee or marine turtle movement.
 - d. All on-site project personnel are responsible for observing water-related activities for the presence of marine turtles and manatees. **All in-water operations, including vessels, shall be shutdown if a marine turtle or manatee comes within 50 feet of the operation.** Activities shall not resume until the animal(s) has moved beyond the 50-foot radius of the project operation, or until 30 minutes elapses if the animal(s) has not reappeared within 50 feet of the operation. Animals shall not be herded away or harassed into leaving.
 - e. Any collision with or injury to a marine turtle or manatee shall be reported immediately to the Florida Fish and Wildlife Conservation Commission (FWC) Hotline at 1-888-404-3922, and to FWC at ImperiledSpecies@myFWC.com. Collision and/or injury should also be reported to the U.S. Fish and Wildlife Service (FWS) in Jacksonville at 1-904-731-3336.
 - f. Temporary signs concerning manatees shall be posted prior to and during all in-water project activities. All signs are to be removed by the Permittee upon completion of the project. Temporary signs that have already been approved for this use by the FWC must be used. One sign which reads *Caution: Boaters* must be posted. A

second sign measuring at least 8 ½" by 11" explaining the requirements for "Idle Speed/No Wake" and the shut down of in-water operations must be posted in a location prominently visible to all personnel engaged in water-related activities. ~~Two of these signs are attached, and signs already approved by the FWC. These signs can~~ be viewed at www.MyFWC.com/manatee. Questions concerning these signs can be sent to the email address listed above.

Caution Boaters
Watch for Manatees



Wildlife Alert:
1-888-404-FWCC(3922)
cell *FWC or #FWC

Report collisions, sick, dead or injured manatees
and any wildlife or boating law violations.

CAUTION: MANATEE HABITAT

All project vessels

IDLE SPEED / NO WAKE

When a manatee is within 50 feet of work
all in-water activities must

SHUT DOWN

Report any collision with or injury to a manatee:



Wildlife Alert:
1-888-404-FWCC(3922)
cell *FWC or #FWC

Notice of Permit Modification
Permit Modification No. 0308009-003-JN
Ponce de Leon Inlet Maintenance Dredging
Page 5 of 9

- ~~g. At least one person shall be designated as a manatee observer when in-water work is being performed. That person shall have experience in manatee observation during dredging activities, and be equipped with polarized sunglasses to aid in observation. The manatee observer shall be on site during all in-water construction activities and advise personnel to cease operation upon sighting a manatee within 50 feet of any in-water construction activity. Two observers who have experience in manatee observation during night-time dredging activity shall be used when nighttime clamshell dredging is conducted during the months of April through November.~~
- ~~h. During clamshell dredging, the dredge operator shall gravity release the clamshell bucket only at the water surface, and only after confirmation that there are no manatees within the safety distance identified in the standard construction conditions.~~
- ~~i. Hydraulic dredging shall be used as much as practicable.~~

After thorough review of your application, staff finds that the proposed modification is not expected to adversely affect water quality or be contrary to the public interest. Staff has also determined that the proposed alteration does not increase the potential for adverse impact on the coastal system, public beach access seaward of the mean high water line or nesting sea turtles and hatchlings and their habitat, and that the proposed alteration does not reduce the design adequacy of the project. Since the proposed modification is not expected to result in any adverse environmental impact or water quality degradation, the **permit is hereby modified** as requested. By copy of this letter, we are notifying all necessary parties of the modification(s).

This letter of approval does not alter the August 3, 2022 expiration date, other Specific or General Conditions, or monitoring requirements of the permit. This letter must be attached to the original permit.

This permit is hereby modified unless a sufficient petition for an administrative hearing is timely filed under Sections 120.569 and 120.57, Florida Statutes (F.S.), as provided below. The procedures for petitioning for a hearing are set forth below. Mediation under Section 120.573, F.S., is not available for this proceeding.

NOTICE OF RIGHTS

A person whose substantial interests are affected by the Department's action may petition for an administrative proceeding (hearing) under Sections 120.569 and 120.57, F.S. The petition must contain the information set forth below and must be filed (received by the clerk) in the Office of General Counsel of the Department at 3900 Commonwealth Boulevard, Mail Station 35, Tallahassee, Florida 32399-3000.

Notice of Permit Modification
Permit Modification No. 0308009-003-JN
Ponce de Leon Inlet Maintenance Dredging
Page 6 of 9

Because the administrative hearing process is designed to redetermine final agency action on the application, the filing of a petition for an administrative hearing may result in further modification of the permit or even a denial of the application. If a sufficient petition for an administrative hearing or request for an extension of time to file a petition is timely filed, this permit modification automatically becomes only proposed agency action on the application subject to the result of the administrative review process. Accordingly, the applicant is advised not to commence construction or other activities under this permit modification until the deadlines noted below for filing a petition for an administrative hearing or request for an extension of time has expired.

Under Rule 62-110.106(4), Florida Administrative Code (F.A.C.), a person whose substantial interests are affected by the Department's action may also request an extension of time to file a petition for an administrative hearing. The Department may, for good cause shown, grant the request for an extension of time. Requests for extension of time must be filed with the Office of General Counsel of the Department at 3900 Commonwealth Boulevard, Mail Station 35, Tallahassee, Florida 32399-3000, before the applicable deadline. A timely request for extension of time shall toll the running of the time period for filing a petition until the request is acted upon. If a request is filed late, the Department may still grant it upon a motion by the requesting party showing that the failure to file a request for an extension of time before the deadline was the result of excusable neglect.

In the event that a timely and sufficient petition for an administrative hearing is filed, other persons whose substantial interests will be affected by the outcome of the administrative process have the right to petition to intervene in the proceeding. Any intervention will be only at the discretion of the presiding judge upon the filing of a motion in compliance with Rule 28-106.205, F.A.C.

In accordance with Rule 62-110.106(3), F.A.C., petitions for an administrative hearing by the applicant must be filed within 14 days of receipt of this written notice. Petitions filed by any persons other than the applicant, and other than those entitled to written notice under Section 120.60(3), F.S., must be filed within 14 days of publication of the notice or within 14 days of receipt of the written notice, whichever occurs first.

Under Section 120.60(3), F.S., however, any person who has asked the Department for notice of agency action may file a petition within 14 days of receipt of such notice, regardless of the date of publication.

The petitioner shall mail a copy of the petition to the applicant at the address indicated above at the time of filing. The failure of any person to file a petition for an administrative hearing within the appropriate time period shall constitute a waiver of that person's right to request an administrative determination (hearing) under Sections 120.569 and 120.57, F.S.

Notice of Permit Modification
Permit Modification No. 0308009-003-JN
Ponce de Leon Inlet Maintenance Dredging
Page 7 of 9

In accordance with Rule 28-106.201, F.A.C., a petition that disputes the material facts on which the Department's action is based must contain the following information:

- (a) The name and address of each agency affected and each agency's file or identification number, if known;
- (b) The name, address, and telephone number of the petitioner; the name, address, and telephone number of the petitioner's representative, if any, which shall be the address for service purposes during the course of the proceeding; and an explanation of how the petitioner's substantial interests are or will be affected by the agency determination;
- (c) A statement of when and how the petitioner received notice of the agency decision;
- (d) A statement of all disputed issues of material fact. If there are none, the petition must so indicate;
- (e) A concise statement of the ultimate facts alleged, including the specific facts that the petitioner contends warrant reversal or modification of the agency's proposed action;
- (f) A statement of the specific rules or statutes that the petitioner contends require reversal or modification of the agency's proposed action, including an explanation of how the alleged facts relate to the specific rules or statutes; and
- (g) A statement of the relief sought by the petitioner, stating precisely the action that the petitioner wishes the agency to take with respect to the agency's proposed action.

A petition that does not dispute the material facts on which the Department's action is based shall state that no such facts are in dispute and otherwise shall contain the same information as set forth above, as required by Rule 28-106.301, F.A.C. Under Sections 120.569(2)(c) and (d), F.S., a petition for administrative hearing must be dismissed by the agency if the petition does not substantially comply with the above requirements or is untimely filed.

This action is final and effective on the date filed with the Clerk of the Department unless a petition is filed in accordance with the above. Upon the timely filing of a petition this order will not be effective until further order of the Department.


This permit modification constitutes an order of the Department. The applicant has the right to seek judicial review of the order under Section 120.68, F.S., by the filing of a notice of appeal under Rule 9.110 of the Florida Rules of Appellate Procedure with the Clerk of the Department in the Office of General Counsel, 3900 Commonwealth Boulevard, Mail Station 35, Tallahassee, Florida 32399-3000; and by filing a copy of the notice of appeal accompanied by the applicable filing fees with the appropriate district court of appeal. The notice of appeal must be filed within 30 days from the date when the final order is filed with the Clerk of the Department.

Notice of Permit Modification
Permit Modification No. 0308009-003-JN
Ponce de Leon Inlet Maintenance Dredging
Page 8 of 9

When there has been no publication of notice of agency action or notice of proposed agency action as prescribed in Rule 62-110.106, F.A.C., a person may request a copy of the agency action. The Department shall upon receipt of such a request, if agency action has occurred, promptly provide the person with notice. The Department does not require notice of this agency action to be published. However, the applicant may elect to publish notice as prescribed in Rule 62-110.106, F.A.C., which constitutes notice to the public and establishes a time period for submittal of any petition.

If you have any questions regarding this matter, please contact Tom Jacobs at the letterhead address (add Mail Station 300) or by telephone at (850) 413-7785.

Sincerely,



Martin K. Seeling
Environmental Administrator
Bureau of Beaches & Coastal Systems

MKS/tj

cc: Russ Jones, USACE
Cheryl Grieb, ECFRPC
Joie Alexander, Volusia County
Patricia Northey, Volusia County
Joyce Cusak, Volusia County
Daniel Fondren, DWRM
Gene Chalecki, DWRM
Roxane Dow, DWRM
Martin Seeling, DWRM
Lainie Edwards, DWRM
Tom Jacobs, DWRM
Robert Brantly, DWRM
El Kromhout, DWRM
Lt. Steve Van Nortwick, FWC, LE

Vladimir Kosmynin, DWRM
Dave Herbster, DEP, Central District Office
David Kriger, CCCL Processor
Alex Reed, DWRM
Guy Weeks, BECP Project Manager, DWRM
Wesley Cich, Field Inspector
Robbin Trindell, FWC, ISMS
Laura DiGruttlo, FWC, CPS
MarineTurtle@MyFWC.com
FWCConservationPlanningServices@myfwc.com
JCP Compliance Officer
DWRM File
Irene Sadowski, USACE

Attachment: Corrected Original Permit



Florida Department of Environmental Protection

Marjory Stoneman Douglas Building
3900 Commonwealth Boulevard
Tallahassee, Florida 32399-3000

Rick Scott
Governor

Jennifer Carroll
Lt. Governor

Herschel T. Vinyard Jr.
Secretary

CONSOLIDATED JOINT COASTAL PERMIT AND SOVEREIGN SUBMERGED LANDS AUTHORIZATION

PERMITTEE:

U.S. Army Corps of Engineers
Attn.: Eric Summa
P.O. Box 4970
Jacksonville, Florida 32232-0019

PERMIT INFORMATION:

Permit Number: 0308009-001-JC

Project Name: Ponce de Leon Inlet
Maintenance Dredging

County: Volusia

Issuance Date: August 3, 2012

Expiration Date: August 3, 2022

REGULATORY AUTHORIZATION:

This permit is issued under the authority of Chapter 161 and Part IV of Chapter 373, Florida Statutes (F.S.), and Title 62, Florida Administrative Code (F.A.C.). Pursuant to Operating Agreements executed between the Department of Environmental Protection (Department) and the water management districts, as referenced in Chapter 62-113, F.A.C., the Department is responsible for reviewing and taking final agency action on this activity.

PROJECT DESCRIPTION:

The project is to conduct maintenance dredging of the Ponce de Leon Inlet entrance channel, Inlet throat, and Inlet channels leading to the Atlantic Intracoastal Waterway (AIWW). Approximately 200,000 cubic yards of shoal material are expected to be removed every 4 years to maintain the federal channel depths. The channels will be maintained to the following maximum depths, which include the design depths, plus 2 feet of allowable overdepth: -17 feet mean lower low water (MLLW) for the entrance channel across the ocean bar; -14 feet MLLW for the Inlet throat; -14 feet MLLW for the southward channel to the AIWW; -14 feet MLLW for Cut-3N, Cut-4N and Cut-5N in the northward channel to the AIWW; and -9 feet MLLW for the remaining northward channel to the AIWW (Cut-6N through Cut-13N). Dredged material will be placed in a nearshore disposal area (D/A), located 1 mile south of the south jetty, for the initial maintenance dredging event only. The landward portion of the D/A will be filled first, and disposal will proceed waterward only as the landward portion reaches capacity.

**Joint Coastal Permit
Ponce de Leon Inlet Maintenance Dredging
Permit No. 0308009-001-JC
Page 2 of 16**

Dredged material from subsequent maintenance dredging events will be placed on the beach, when sufficient beach-quality material and funding are available. A permit modification will be required for the placement of dredged material on the beach.

PROJECT LOCATION:

The maintenance dredging area is located at Ponce de Leon Inlet and the interior channels connecting the Inlet to the AIWW. The nearshore disposal area is located one mile south of the Inlet, with a landward edge along the -12-foot mean lower low water (MLLW) contour line. The project is located in Volusia County, Sections 32 and 37, Township 16 South, Range 34 East, in Ponce de Leon Inlet and the Atlantic Ocean, Class III Waters.

PROPRIETARY AUTHORIZATION:

This activity also requires a proprietary authorization, as the activity is located on sovereign submerged lands held in trust by the Board of Trustees of the Internal Improvement Trust Fund (Board of Trustees), pursuant to Article X, Section 11 of the Florida Constitution, and Sections 253.002 and 253.77, F.S. The activity is not exempt from the need to obtain a proprietary authorization. The Board of Trustees delegated, to the Department, the responsibility to review and take final action on this request for proprietary authorization in accordance with Section 18-21.0051, F.A.C., and the Operating Agreements executed between the Department and the water management districts, as referenced in Chapter 62-113, F.A.C. This proprietary authorization has been reviewed in accordance with Chapter 253, F.S., Chapter 18-21, F.A.C., and the policies of the Board of Trustees.

As staff to the Board of Trustees, the Department has reviewed the project described above, and has determined that the dredged material disposal activity qualifies for a Letter of Consent to use sovereign, submerged lands, as long as the work performed is located within the boundaries as described herein and is consistent with the terms and conditions herein. Therefore, consent is hereby granted to the U.S. Army Corps of Engineers (Corps), pursuant to Chapter 253.77, F.S., to perform the activity on the specified sovereign submerged lands.

The Department acknowledges that maintenance dredging of the inlet falls within one of the federal powers listed in the Submerged Lands Act under 43 USC 1311(d) or 43 USC 1314, and, under those provisions, the Corps needs no authorization from the Board of Trustees to utilize sovereignty submerged lands for that activity. However, under the provisions of the Coastal Zone Management Act (16 USC 1451-1465), this activity requires Florida's concurrence with a determination of consistency with the sovereignty submerged lands provisions of Florida's approved Coastal Management Program prior to federal approval of the proposed activity. The State has

determined that the activity is consistent with the sovereignty submerged lands provisions of Florida's approved Coastal Management Program.

COASTAL ZONE MANAGEMENT:

This permit constitutes a finding of consistency with Florida's Coastal Zone Management Program, as required by Section 307 of the Coastal Zone Management Act.

WATER QUALITY CERTIFICATION:

This permit constitutes certification of compliance with state water quality standards pursuant to Section 401 of the Clean Water Act, 33 U.S.C. 1341.

AGENCY ACTION:

The above named Permittee is hereby authorized to construct the work outlined in the project description and project location of this permit and shown on the approved permit drawings, plans and other documents attached hereto. This agency action is based on the information submitted to the Department as part of the permit application, and adherence with the final details of that proposal shall be a requirement of the permit. **This permit and authorization to use sovereign submerged lands are subject to the General Conditions and Specific Conditions, which are a binding part of this permit and authorization.** Both the Permittee and their Contractor are responsible for reading and understanding this permit (including the permit conditions and the approved permit drawings) prior to commencing the authorized activities, and for ensuring that the work is conducted in conformance with all the terms, conditions and drawings.

GENERAL CONDITIONS:

1. This permit, including its general and specific conditions, must be construed in light of the February 28, 2006 Interagency Coordination Agreement for Civil Works Projects (ICA) between the Department and the Corps. As recognized in the ICA, the Department has the authority to include reasonable conditions in this permit. All of the conditions in this permit, both general and specific, are enforceable to the extent sovereign immunity has been waived under 33 U.S.C. §§ 1323 and 1344(t). The ICA is incorporated herein by reference.
2. All activities approved shall be implemented as set forth in the drawings incorporated by reference and in compliance with the conditions and requirements of this document. The Corps shall notify the Department in writing of any anticipated changes in:
 - a) operational plans;

- b) project dimensions, size or location;
- c) ability to adhere to permit conditions;
- d) project description included in the permit;
- e) monitoring plans.

If the Department determines that a modification to the permit is required then the Corps shall apply for and obtain the modification. Department approval of the modification shall be obtained prior to implementing the change, unless the change is determined by the Department to reduce the scope of work from that authorized under the original permit, and will not affect compliance with permit conditions or monitoring requirements.

3. If, for any reason, the Corps does not comply with any condition or limitation specified herein, the Corps shall immediately provide the Department with a written report containing the following information:
 - a) a description of and cause of noncompliance;
 - b) the period of noncompliance, including dates and times;
 - c) impacts resulting or likely to result from the non-compliance;
 - d) steps being taken to correct the non-compliance; and
 - e) the steps being taken to reduce, eliminate, and prevent recurrence of the noncompliance.

Compliance with the provisions of this condition shall not preclude the Department from taking any enforcement action allowed under state law with respect to any non-compliance.

4. The Corps shall obtain any applicable licenses, permits, or other authorizations which may be required by federal, state, local or special district laws and regulations. Nothing herein constitutes a waiver or approval of other Department permits or authorizations that may be required for other aspects of the total project.
5. Nothing herein conveys to the Corps or creates in the Corps any property right, any interest in real property, any title to land or water, constitutes State recognition or acknowledgment of title, or constitutes authority for the use of Florida's sovereign submerged lands seaward of the mean high-water line or an established erosion control line, unless herein provided, and the necessary title, lease, easement, or other form of consent authorizing the proposed use has been obtained from the State.

6. Any delineation of the extent of a wetland or other surface water submitted as part of the application, including plans or other supporting documentation, shall not be considered specifically approved unless a specific condition of this authorization or a formal determination under section 373.421(2), F.S., provides otherwise.
7. Nothing herein authorizes any entrance upon or activities on property which is not owned or controlled by the Corps or local sponsor, or conveys any vested rights or any exclusive privileges.
8. This document or a copy thereof, complete with all conditions, attachments, modifications, and time extensions shall be kept at the work site of the authorized activity. The Corps shall require the contractor to review this document prior to commencement of the authorized activity.
9. The Corps specifically agrees to allow Department personnel with proper identification, at reasonable times and in compliance with Corps specified safety standards access to the premises where the authorized activity is located or conducted for the purpose of ascertaining compliance with the terms of this document and with the rules of the Department and to have access to and copy any records that must be kept; to inspect the facility, equipment, practices, or operations regulated or required; and to sample or monitor any substances or parameters at any location reasonably necessary to assure compliance. Reasonable time may depend on the nature of the concern being investigated.
10. At least forty-eight (48) hours prior to the commencement of authorized activity, the Corps shall submit to the Department a written notice of commencement of activities indicating the anticipated start date and the anticipated completion date.
11. If historic or archaeological artifacts such as, but not limited to, Indian canoes, arrow heads, pottery or physical remains, are discovered at any time on the project site, the Corps shall immediately stop all activities in the immediate area which disturb the soil and notify the Department and the State Historic Preservation Officer. In the event that unmarked human remains are encountered during permitted activities, all work shall stop in the immediate area and the proper authorities notified in accordance with Section 872.05, *Florida Statutes*.
12. Within a reasonable time after completion of construction activities authorized by this permit, the Corps shall submit to the Department a written statement of

completion. This statement shall notify the Department that the work has been completed as authorized and shall include a description of the actual work completed. The Department shall be provided, if requested, a copy of any as-built drawings required of the contractor or survey performed by the Corps.

SPECIFIC CONDITIONS:

1. The Permittee and the Department, within their respective authorities and funding, shall ensure that beach compatible dredged material is placed on Florida's beaches, consistent with Florida's beach management plan adopted pursuant to Chapter 161, F.S. and other beneficial uses criteria as may be specified by the Department and applicable federal standards. The authorized activity includes a one-time placement of dredged beach-quality material in the nearshore disposal area. Future maintenance dredging events will be required to place beach-quality dredged material on the beach per the Ponce de Leon Inlet Management Plan of 1997. If the Permittee desires to perform additional maintenance dredging events under this authorization, a permit modification will be necessary.
2. Dredged material shall initially be placed at the -12-foot MLLW contour of the nearshore disposal area. When the -12-foot MLLW contour reaches capacity, the dredged material shall be deposited waterward in the disposal area, until the volume of material is exhausted, but shall not be placed seaward of the -18-foot MLLW contour.
3. The Permittee shall not store or stockpile tools, equipment, materials, etc., within littoral zones or elsewhere within surface waters of the state without prior written approval from the Department. Storage, stockpiling or access of equipment on, in, over or through seagrass (or other aquatic vegetation) beds, wetlands or vegetated dunes is prohibited unless within a work area or ingress/egress corridor specifically approved by this permit. Anchoring or spudding of vessels and barges within beds of aquatic vegetation or over hardbottom areas is also prohibited.
4. The Permittee shall not conduct project operations or store project-related equipment in, on or over dunes, or otherwise impact dune vegetation, outside the approved staging, beach access and dune restoration areas designated in the permit drawings.
5. **Pre-Construction Conference.** The Permittee shall conduct a pre-construction conference to review the specific conditions and monitoring requirements of this permit with Permittee's contractors, the engineer of record and the JCP.

**Joint Coastal Permit
Ponce de Leon Inlet Maintenance Dredging
Permit No. 0308009-001-JC
Page 7 of 16**

Compliance Officer (or designated alternate) prior to each construction event. In order to ensure that appropriate representatives are available, at least twenty-one (21) days prior to the intended commencement date for the permitted construction, the Permittee is advised to contact the Department, and the other agency representatives listed below:

DEP, Bureau of Beaches & Coastal Systems
JCP Compliance Officer
Mail Station 300
3900 Commonwealth Boulevard
Tallahassee, Florida 32399-3000
phone: (850) 414-7716
e-mail: JCPCompliance@dep.state.fl.us

DEP Central District Office
Submerged Lands and Environmental Resources Program
3319 Maguire Boulevard
Orlando, Florida 32803-3767
phone: (407) 894-7555

Imperiled Species Management Section
Florida Fish & Wildlife Conservation Commission
620 South Meridian Street
Tallahassee, Florida 32399-1600
phone: (850) 922-4330
fax: (850) 921-4369 or email: marineturtle@myfwc.com

The Permittee is also advised to schedule the pre-construction conference at least a week prior to the intended commencement date. At least seven (7) days in advance of the pre-construction conference, the Permittee shall provide written notification, advising the participants (listed above) of the agreed-upon date, time and location of the meeting, and also provide a meeting agenda and a teleconference number.

6. **Pre-Construction Submittals.** At least fourteen (14) days prior to the date of the pre-construction conference (as required above), the Permittee shall submit the final plans and specifications for this project, which must be consistent with the activity description of this permit and the approved permit drawings. The Permittee shall point out any deviations from the activity description or the approved permit drawings, and any significant changes would require a permit modification. Submittal shall include one (1) hardcopy (sized 11 inches by 17

inches or greater, with all text legible) and one (1) electronic copy of the final plans and specifications. The plans and specifications shall be accompanied by a letter indicating the project name, the permit number, the type of construction activity, the specific type of equipment to be used, the anticipated volume of material to be moved (if applicable) and the anticipated schedule. Further, the Permittee shall specify any anticipated sites that will be used (such as a disposal or re-use location) and appropriate contact information for those facilities. The final plans and specifications submitted under this condition must comply with all conditions set forth in this permit.

Fish and Wildlife Protective Measures for Dredging


7. **Manatee and Marine Turtle Protection Conditions:** During all construction authorized by this permit, the Permittee shall comply with the following conditions intended to protect manatees and marine turtles from direct project effects:
 - a. All personnel associated with the project shall be instructed about the presence of marine turtles, manatees and manatee speed zones, and the need to avoid collisions with (and injury to) these protected marine species. The Permittee shall advise all construction personnel that there are civil and criminal penalties for harming, harassing, or killing manatees which are protected under the Marine Mammal Protection Act, the Endangered Species Act, and the Florida Manatee Sanctuary Act.
 - b. All vessels associated with the construction project shall operate at "Idle Speed/No Wake" at all times while in the immediate area and while in water where the draft of the vessel provides less than a four-foot clearance from the bottom. All vessels will follow routes of deep water whenever possible.
 - c. If siltation or turbidity barriers are used, they shall be made of material in which manatees and marine turtles cannot become entangled, shall be properly secured, and shall be regularly monitored to avoid entanglement or entrapment. Barriers must not impede manatee or marine turtle movement.
 - d. All on-site project personnel are responsible for observing water-related activities for the presence of marine turtles and manatees. **All in-water operations, including vessels, shall be shutdown if a marine turtle or manatee comes within 50 feet of the operation.** Activities shall not resume until the animal(s) has moved beyond the 50-foot radius of the project operation, or until 30 minutes elapses if the animal(s) has not reappeared

within 50 feet of the operation. Animals shall not be herded away or harassed into leaving.

- e. Any collision with or injury to a marine turtle or manatee shall be reported immediately to the Florida Fish and Wildlife Conservation Commission (FWC) Hotline at 1-888-404-3922, and to FWC at

ImperiledSpecies@myFWC.com. Collision and/or injury should also be reported to the U.S. Fish and Wildlife Service (FWS) in Jacksonville at 1-904-731-3336.

- f. Temporary signs concerning manatees shall be posted prior to and during all in-water project activities. All signs are to be removed by the Permittee upon completion of the project. Temporary signs that have already been approved for this use by the FWC must be used. One sign which reads *Caution: Boaters* must be posted. A second sign measuring at least 8 ½" by 11" explaining the requirements for "Idle Speed/No Wake" and the shut down of in-water operations must be posted in a location prominently visible to all personnel engaged in water-related activities. Two of these signs are attached, and signs already approved by the FWC can be viewed at www.MyFWC.com/manatee. Questions concerning these signs can be sent to the email address listed above.





- g. At least one person shall be designated as a manatee observer when in-water work is being performed. That person shall have experience in manatee observation during dredging activities, and be equipped with polarized sunglasses to aid in observation. The manatee observer shall be on site during all in-water construction activities and advise personnel to cease operation upon sighting a manatee within 50 feet of any in-water construction activity. Two observers who have experience in manatee observation during night time dredging activity shall be used when nighttime clamshell dredging is conducted during the months of April through November.
 - h. During clamshell dredging, the dredge operator shall gravity-release the clamshell bucket only at the water surface, and only after confirmation that there are no manatees within the safety distance identified in the standard construction conditions.
 - i. Hydraulic dredging shall be used as much as practicable.
8. **Marine Turtle Protection Conditions for Dredging Activities:** The following recommendations are made to ensure consistency with the Florida Coastal Zone Management Act, specifically with Section 379.2431(1), F.S.

In the event a hopper dredge is utilized, the following requirements shall be met in conjunction with the Terms and Conditions of the applicable National Marine Fisheries Service (NMFS) Regional Biological Opinion for Hopper Dredging (South Atlantic):


- a. Handling of sea turtles captured during hopper dredging projects shall be conducted only by persons with prior experience and training in these activities and who is duly authorized to conduct such activities as a NMFS-approved sea turtle observer or have

Joint Coastal Permit
Ponce de Leon Inlet Maintenance Dredging
Permit No. 0308009-001-JC
Page 11 of 16

submitted documentation to the Corps of meeting the FWC Marine Turtle Conservation Guidelines specific to stranding activities (Section 3). The Corps will forward documentation to FWC and the Department for review concurrent with the submission of the contractor Environmental Protection Plan.

- b. Corps staff or their designee that transport live or dead marine turtles or marine turtle parts into, out of or within, the state of Florida shall notify FWC in writing specifying the number, species of sea turtle, type of specimen, and the destination after transport is complete. Before transport, if the turtle is believed to be alive, Corps staff or their designee will coordinate with FWC and/or NMFS to determine the appropriate facility to receive live sea turtles for rehabilitation. Corps staff or their designee shall abide by the State of Florida's FWC Marine Turtle Conservation Guidelines (<http://www.myfwc.com/wildlifehabitats/managed/sea-turtles/conservation-guidelines/>) specific to transport of live stranded turtles.
 - c. *Dredging Pumps*: Standard operating procedure shall be that dredging pumps shall be disengaged by the operator, or the draghead bypass valve shall be open and in use when the dragheads are not firmly on the bottom, to minimize impingement or entrainment of sea turtles within the water column. This precaution is especially important during the cleanup phase of dredging operations.
 - d. *Sea Turtle Deflecting Draghead*: A state-of-the-art rigid deflector draghead shall be used on all hopper dredges in all channels at all times of the year.
 - e. The Sea Turtle Stranding and Salvage Network (STSSN) Coordinator shall be notified at 1-904-573-3930 or via e-mail at Allen.Foley@myfwc.com of the start-up and completion of hopper dredging operations. In the event of capturing or recovering marine turtles or marine turtle parts, the STSSN should be contacted at 1-888-404-FWCC (3922).
 - f. Relocation trawling or non-capture trawling shall be implemented in accordance with the applicable NMFS Biological Opinion and Incidental Take authorization. Any activity involving the use of nets to harass and/or to capture and handle marine turtles in Florida waters requires a Marine Turtle Permit from FWC.
 - i. A summary (use FWC Trawl Report spreadsheet, attached) of all trawling activity, including non-capture trawling, and all turtles captured in Florida waters, including all measurements, the latitude and longitude (in decimal degrees) of captures and tow start-stop points, and times for the start-stop points of the tows, including those tows on which no turtles are captured, shall be submitted to MTP@myfwc.com by January 15 of the following year.
9. **Project Lighting for Marine Turtle Protection**: Direct lighting of the beach and nearshore waters shall be limited to the immediate construction area during the

marine turtle nesting season and shall comply with safety requirements. Lighting on offshore or onshore equipment shall be minimized through reduction, shielding, lowering, and appropriate placement to avoid excessive illumination of the water's surface and nesting beach while meeting all Coast Guard, EM 385-1-1, and OSHA requirements. Light intensity of lighting equipment shall be reduced to the minimum standard required by OSHA for General Construction areas, in order not to misdirect sea turtles. Shields shall be affixed to the light housing and be large enough to block light from all lamps from being transmitted outside the construction area (**Figure below**).



- Equipment Storage and Placement:** Staging areas for construction equipment shall be located off the beach, if off-beach staging areas are available, during the sea turtle nesting season. Nighttime storage of construction equipment not in use shall be off the beach. In addition, all construction pipes that are placed on the beach shall be located as far landward as possible without compromising the integrity of the existing or reconstructed dune system. Pipes placed parallel to the vegetation line shall be 5 to 10 feet away from the toe of the vegetation line. Temporary storage of pipes shall be off the beach to the maximum extent possible. If the pipes shall be on the beach, they shall be placed in a manner that will minimize the impact to nesting habitat and shall not compromise the integrity of the dune systems. If it will be necessary to extend construction pipes past a known migratory bird nesting site or over-wintering area for piping plovers, then whenever possible, those pipes should be placed landward of the site before birds are active in that area. No pipe or sand shall be placed within or seaward of a migratory bird nesting site during the migratory bird nesting season.

11. **Marine Turtle or Nest Encounters:** Upon locating a dead or injured sea turtle adult, hatchling or egg that may have been harmed or destroyed as a direct or indirect result of the project, the Corps and/or local sponsor shall be responsible for notifying FWC Wildlife Alert at 1-888-404-FWCC (3922). Care shall be taken in handling injured sea turtles or their eggs to ensure effective treatment or disposition, and in handling dead specimens to preserve biological materials in the best possible state for later analysis. In the event a marine turtle nest is excavated during construction activities, the permitted person responsible for egg relocation for the project shall be notified immediately so the eggs can be moved to a suitable relocation site.
12. The following species are protected by the Federal Migratory Bird Treaty Act, as well as Chapter 379, F.S., which prohibits the take and/or harassment of migratory birds and their nests and eggs for the following species: piping plover (*Charadrius melodus*), American oystercatcher (*Haematopus palliatus*), black skimmer (*Rynchops niger*), brown pelican (*Pelecanus occidentalis*), little blue heron (*Egretta caerulea*), snowy egret (*Egretta thula*), tricolored heron (*Egretta tricolor*), white ibis (*Eudocimus albus*), Wilson's plover (*Charadrius wilsonia*).
13. **Environmental Protection Plan:** The contractor's Environmental Protection Plan (EPP) shall be submitted for review and comment to the Department in coordination with FWC prior to any construction activity. This plan shall include monitoring of nesting migratory birds and marine turtle nests onsite during construction, as well as steps that will be followed to address any unavoidable take of migratory birds and/or marine turtles should that occur.

Monitoring Required

14. **Water Quality - Turbidity** shall be monitored as follows:

Monitoring for turbidity shall be conducted by an individual with professional experience conducting turbidity monitoring for coastal dredging projects. The monitoring shall continue for the duration of the dredging and filling activities. This monitoring is designed for a hopper dredge and nearshore placement. A permit modification would be required to adjust the turbidity monitoring if a pipeline dredge will be used or beach placement is proposed.

Units: Nephelometric Turbidity Units (NTUs).

Frequency: Twice daily, during separate hopper dredge loads.

Dredge Site: While the maximum turbidity plume, generated by overflow from the hopper, extends to the edge of the mixing zone.

Nearshore Disposal Site: During flood tide, while the maximum turbidity plume, generated by discharge of sediment from the hopper, extends to the edge of the mixing zone.

Location: Background: At the surface and mid-depth, clearly outside the influence of any artificially generated turbidity plume.

Dredge Site: approximately 300 meters upcurrent from the dredge.

Nearshore Disposal Site: approximately 300 meters upcurrent of the dredged material placement template, and the same distance offshore as the associated compliance sample.

Compliance: At the surface and mid-depth, within the densest portion of any turbidity plume generated by this project.

Dredge Site: Samples shall be collected 150 meters downcurrent from the overflowing hopper dredge, in the densest portion of the turbidity plume.

Nearshore Disposal Site: Samples shall be collected where the densest portion of the turbidity plume extends, (no more than) 150 meters from the point where the dredged material is discharged into the Atlantic Ocean.

Turbidity Reports. All turbidity monitoring data shall be submitted within one week of collection, along with documents containing the following information:

- a. time of day samples were taken;
- b. dates of sampling and analysis;
- c. depth of water body;
- d. depth of each sample;
- e. antecedent weather conditions, including wind direction and velocity;
- f. tidal stage and direction of flow;

- g. water temperature;
- h. a map indicating the sampling (compliance and background) locations;
- i. a statement describing the methods used in collection, handling, storage and analysis of the samples;
- j. a statement by the individual responsible for implementation of the sampling program concerning the authenticity, precision, limits of detection, calibration of the meter and accuracy of the data.

Monitoring reports shall be emailed to the JCP Compliance Officer at JCPCCompliance@dep.state.fl.us. Failure to submit reports in a timely manner constitutes grounds for revocation of the permit. When submitting this information to the Department, on the submittal cover page and at the top of each page of the report, please state: "This information is provided in partial fulfillment of the monitoring requirements in Permit No. 0308009-001-JC, Ponce de Leon Inlet Maintenance Dredging."

Calibration: The instruments used to measure turbidity shall be fully calibrated prior to, but within one month of, the commencement of the current dredging and filling activities, and at least once a month throughout those activities. Calibration shall be verified each morning prior to use, and after each time the instrument is turned on, using a turbidity "standard" that is different from the one used during calibration.

The compliance locations given above shall be considered the limits of the temporary mixing zone for turbidity allowed during construction. If monitoring reveals turbidity levels at compliance sites that are greater than 29 NTUs above background levels, construction activities shall **cease immediately** and not resume until corrective measures have been taken and turbidity has returned to acceptable levels. Any such occurrence shall also be immediately reported to the JCP Compliance Officer in Tallahassee at (850) 414-7716 or JCPCCompliance@dep.state.fl.us and the Department's Central District office in Orlando, Florida, at (407) 894-7555.

Any project-associated discharge other than dredging or authorized placement (e.g., scow leakage) shall also be monitored as close to the source as possible every hour until background turbidity levels return or until otherwise directed by the Department. The Permittee shall notify the Department, by separate email to the JCP Compliance Officer, of such an event within 24 hours of the time the Permittee first becomes aware of the discharge. The subject line of the email

shall state "PROJECT-ASSOCIATED DISCHARGE-OTHER", and include the Project Name and the Permit Number.

15. All reports or notices relating to this permit shall be sent to the Department, Bureau of Beaches and Coastal Systems, JCP Compliance Officer, 3900 Commonwealth Boulevard, Mail Station 300, Tallahassee, Florida 32399-3000 (e-mail address: JCPCompliance@dep.state.fl.us) and the Department's Central District Office, at the following mailing address:

DEP Central District Office
Submerged Lands and Environmental Resources Program
3319 Maguire Boulevard
Orlando, Florida 32803-3767

Executed in Tallahassee, Florida.

STATE OF FLORIDA DEPARTMENT
OF ENVIRONMENTAL PROTECTION



Gene Chalecki, Acting Bureau Chief
Bureau of Beaches and Coastal Systems

FILING AND ACKNOWLEDGMENT

FILED, on this date, pursuant to Section 120.52, Florida Statutes, with the designated Department Clerk, receipt of which is hereby acknowledged.

 8/3/12
Deputy Clerk Date

Prepared by Tom Jacobs.

Attachments: Approved Permit Drawings (25 pages)

DESIGN AUTHENTICATION

PROJECT: Ponce de Leon Inlet, Volusia County, FL (Maintenance Dredging Ponce de Leon Inlet with nearshore placement)

ATTACHED PLAN SHEETS: 1 through 24

The attached plans were prepared by the Jacksonville District, U.S. Army Corps of Engineers (USACE). The initials or signatures and registrations designations of the signatory below or that appear on these project documents are within the scope of employment as required by USACE Engineering Regulation 1110-1-8152, PROFESSIONAL REGISTRATION, 8 Aug 1995, and are not made in the individual capacity of the signatories.

USACE employee signatures are provided in support of the "Interagency Coordination Agreement for Civil Works Projects", signed 28 Feb 2006 by the Florida Department of Environmental Protection, the USACE Jacksonville District, and USACE Mobile District.

These plans are for permitting purposes only, and are not for construction.



Richard I. McMillen, P.E.
Chief, Navigation Branch
Operations Division
GA # 23351


DATE

PERMIT # 308009001

PONCE DE LEON INLET VOLUSIA COUNTY, FLORIDA MAINTENANCE DREDGING, 12-FOOT PROJECT

INDEX TO PLATES	
1	INDEX TO PLATES, LEGEND, AND ABBREVIATIONS
2	PLATE LAYOUT AND SURVEY NOTES
3	PLAN VIEW: CUT-1A STA. 00+00 TO CUT-1A STA. 16+47
4	PLAN VIEW: CUT-1A STA. 16+47 TO CUT-1A STA. 33+96
5	PLAN VIEW: CUT-1A STA. 33+96 TO CUT-1A STA. 51+73
6	PLAN VIEW: CUT-1A STA. 51+73 TO CUT-2A STA. 03+32
7	PLAN VIEW: CUT-2A STA. 03+32 TO CUT-6N STA. 06+17
8	PLAN VIEW: CUT-6N STA. 06+17 TO CUT-7N STA. 08+67
9	PLAN VIEW: CUT-7N STA. 08+67 TO CUT-9N STA. 03+69
10	PLAN VIEW: CUT-8N STA. 03+69 TO CUT-9N STA. 14+52
11	PLAN VIEW: CUT-8N STA. 14+52 TO CUT-10N STA. 03+88
12	PLAN VIEW: CUT-10N STA. 03+88 TO CUT-11N STA. 13+78
13	PLAN VIEW: CUT-11N STA. 13+78 TO CUT-13N STA. 04+35
14	PLAN VIEW: CUT-13N STA. 04+35 TO NORTHERN LIMIT
15	PLAN VIEW: CUT-1S STA. 13+52 TO CUT-2S STA. 07+31
16	PLAN VIEW: CUT-2S STA. 07+31 TO CUT-2S STA. 18+56
17	PLAN VIEW: CUT-2S STA. 18+56 TO CUT-3S STA. 09+18
18	PLAN VIEW: CUT-3S STA. 09+18 TO CUT-3S STA. 21+73
19	PLAN VIEW: CUT-3S STA. 21+73 TO END OF PROJECT
20	CROSS SECTIONS: CUT-1A STA. 10+00 AND CUT-3N STA. 5+00
21	CROSS SECTIONS: CUT-5N STA. 4+00 AND CUT-12N STA. 5+00
22	CROSS SECTIONS: CUT-2S STA. 10+00 AND CUT-3S STA. 18+00
23	NEARSHORE PLACEMENT AREA
24	NEARSHORE CROSS SECTIONS



PERMIT # 308009001



WQC PLATES
NOT FOR CONSTRUCTION

DEPARTMENT OF THE ARMY
JACKSONVILLE DISTRICT, CORPS OF ENGINEERS
JACKSONVILLE, FLORIDA

FILE NAME:	DWN BY: GMK	GENERAL NOTES:
DATED: FEBRUARY 2012	DSN BY: GMK/SR	
SCALE: AS SHOWN	CRD BY: SR	

VOLUSIA COUNTY, FL
MAINTENANCE DREDGING
PONCE DE LEON INLET
PROJECT COVER SHEET,
LEGEND, AND INDEX

PLATE:

01



DEP CONTROL MONUMENTS (NAD 83)

NORTH BEACH PLACEMENT LIMITS

MONUMENT	X	Y
T-140	677083.46	1730906.62
T-141	677572.17	1730113.55
R-142	678337.11	1729367.65
R-143	678862.81	1728696.58
R-144	679380.63	1727847.52
R-145	679907.06	1727144.70
R-146	680512.70	1726371.37
T-147	681037.32	1725569.47
R-148	681570.51	1724827.46

DEP CONTROL MONUMENTS (NAD 83)

SOUTH BEACH PLACEMENT LIMITS

MONUMENT	X	Y
R-158	687001.63	1715414.08
R-159	687374.93	1714513.21
R-160	687826.04	1713632.23
R-161	688252.54	1712766.15
R-162	688737.25	1711945.21
R-163	689102.61	1711006.81
R-164	689605.27	1710168.76
R-165	690044.83	1709340.91
R-166	690494.33	1708574.78
R-167	690958.46	1707815.31
R-168	691344.19	1707083.51
R-169	691794.98	1706371.95
R-170	692201.48	1705693.18
R-171	692593.62	1704426.75
R-172	693175.80	1703327.40
R-173	693550.02	1702537.25
R-174	694020.97	1701679.25
R-175	694473.85	1700852.03
R-176	695003.64	1700038.28
R-177	695454.77	1699145.70

MAP SHEET NOTES




REFER TO SURVEY NUMBER: 10-170
 ELEVATIONS ARE IN FEET AND TENTHS AND REFER TO NOAA'S REPORTED MLLW OF THE 1983-2001 TIDAL EPOCH.
 TIDAL REDUCTIONS WERE OBTAINED UTILIZING REAL-TIME KINEMATIC GPS AND REFERENCED TO MLLW (Volusia-Beach) (see PortCanaveral-07 Jun 02 010.MD).
 ALL ELEVATIONS ARE BELOW THE CHART DATUM UNLESS PRECEDED BY A (+) SIGN.
 PLANE COORDINATES ARE BASED ON THE TRANSVERSE MERCATOR PROJECTION FOR THE EAST ZONE OF FLORIDA AND REFERENCED TO THE NORTH AMERICAN DATUM OF 1983 (NAD 83).
 THIS SURVEY WAS PERFORMED USING REAL-TIME KINEMATIC GPS POSITIONING WITH THE FOLLOWING REFERENCE BASE LOCATION:
 REFERENCE BASE LOCATED AT 972 1147 A
 NORTHING: 1719483.20'
 EASTING: 683175.164'
 NAVDS ELEVATION: 3.83'

*TIDE STAFF LOCATED FROM 972 1147 TIDAL 1/4 (90' MLLW)
 VERTICAL MEASUREMENTS WERE MADE USING A ROSS SMART SOUNDOR 435 FREQUENCY 28 KHZ AND 200 KHZ SINGLE BEAM TRANSDUCER.

SURVEY VESSEL STATION	DATE OF SURVEY	CUT	BASE
SB-32	16 NOV 2010	CUT 13M SW CUT 28 15	972 1147 A
SB-32	17 NOV 2010	CUT 5N 4N CUT 1A 3A	972 1147 A
SB-32	18 NOV 2010	CUT LONGITUDINALE	972 1147 A

THE INFORMATION DEPICTED ON THIS MAP REPRESENTS THE RESULTS OF SURVEYS MADE ON THE DATES INDICATED ABOVE AND CAN ONLY BE CONSIDERED AS INDICATING THE GENERAL CONDITIONS AT THAT TIME. THIS CHART IS SOLELY FOR THE DISTRIBUTION OF AVAILABLE DEPTH AT THE TIME OF SURVEY.

SURVEY ACCURACY STANDARDS, QUALITY CONTROL, AND QUALITY ASSURANCE REQUIREMENTS WERE FOLLOWED DURING THIS SURVEY IN ACCORDANCE WITH USACE EM 1110-2-1003, HYDROGRAPHIC SURVEYING, 1 JAN 02.



BENCHMARK	NAVD ELEV (FT)
972 1147 TIDAL 1	3.83
EXTERAPORT	4.57
PT 25	4.41

SYM	SYMBOL
1	LOWEST SEASON
2	GREEN DAYBEACON
3	RED DAYBEACON
4	RED LIGHTED BUOY
5	GREEN LIGHTED BUOY
6	CAN BUOY
7	MAN BUOY
8	TIDE STAFF

PERMIT # 308009001




WQC PLATES
 NOT FOR CONSTRUCTION
 DEPARTMENT OF THE ARMY
 JACKSONVILLE DISTRICT, CORPS OF ENGINEERS
 JACKSONVILLE, FLORIDA

FILE NAME:	OWN BY:
DATED:	GMK
AS SHOWN	DSN BY:
	GMK/SR
	CKD BY:
	SR

VOLUSIA COUNTY, FLORIDA
MAINTENANCE DREDGING
PONCE DE LEON INLET
 PAGE LAYOUT
 AND SURVEY NOTES

PLATE:
 02



US Army Corps
of Engineers
Jacksonville District

WQC PLATES
NOT FOR CONSTRUCTION
DEPARTMENT OF THE ARMY
JACKSONVILLE DISTRICT, CORPS OF ENGINEERS
JACKSONVILLE, FLORIDA


FILE NAME:
DATE: FEBRUARY 2012
SCALE: AS SHOWN

DWN BY: GMK
DSN BY: GMK/SR
CHK BY: SR

GENERAL NOTES:
- CONTOURS SHOWN ARE AT 2 FOOT INTERVALS
- RED CONTOURS ARE ABOVE PROJECT DEPTH
- BLUE CONTOURS ARE BELOW PROJECT DEPTH

VOLUSIA COUNTY, FL
MAINTENANCE DREDGING
PONCE DE LEON INLET

PLATE:
03



WQC PLATES
NOT FOR CONSTRUCTION
 DEPARTMENT OF THE ARMY
 JACKSONVILLE DISTRICT, CORPS OF ENGINEERS
 JACKSONVILLE, FLORIDA


FILE NAME:
 DATE: FEBRUARY 2012
 SCALE:
 AS SHOWN

DWN BY: GMK
 DSN BY: GMK/SR
 CKD BY: SR


GENERAL NOTES:
 - CONTOURS SHOWN ARE AT 2 FOOT INTERVALS
 - RED CONTOURS ARE ABOVE PROJECT DEPTH
 - BLUE CONTOURS ARE BELOW PROJECT DEPTH

VOLUSIA COUNTY, FL
MAINTENANCE DREDGING
PONCE DE LEON INLET

PLATE:
04



 US Army Corps of Engineers Jacksonville District	WQC PLATES NOT FOR CONSTRUCTION	FILE NAME: DWN BY: GMK	GENERAL NOTES: - CONTOURS SHOWN ARE AT 2 FOOT INTERVALS - RED CONTOURS ARE ABOVE PROJECT DEPTH - BLUE CONTOURS ARE BELOW PROJECT DEPTH	VOLUSIA COUNTY, FL	PLATE: 05
	DEPARTMENT OF THE ARMY JACKSONVILLE DISTRICT, CORPS OF ENGINEERS JACKSONVILLE, FLORIDA	DATED: FEBRUARY 2012		DSN BY: GMK/SR	MAINTENANCE DREDGING PONCE DE LEON INLET
	SCALE: AS SHOWN	CRD BY: SR			



US Army Corps
of Engineers
Jacksonville District

WQC PLATES
NOT FOR CONSTRUCTION
DEPARTMENT OF THE ARMY
JACKSONVILLE DISTRICT, CORPS OF ENGINEERS
JACKSONVILLE, FLORIDA


FILE NAME:
DATED: FEBRUARY 2012
SCALE: AS SHOWN

DWN BY: GMK
DSN BY: GMK/SR
CRD BY: SR

GENERAL NOTES:
- CONTOURS SHOWN ARE AT 2 FOOT INTERVALS
- RED CONTOURS ARE ABOVE PROJECT DEPTH
- BLUE CONTOURS ARE BELOW PROJECT DEPTH

VOLUSIA COUNTY, FL
**MAINTENANCE DREDGING
PONCE DE LEON INLET**

PLATE:
06



WQC PLATES
NOT FOR CONSTRUCTION
 DEPARTMENT OF THE ARMY
 JACKSONVILLE DISTRICT, CORPS OF ENGINEERS
 JACKSONVILLE, FLORIDA


FILE NAME:
 DATE: FEBRUARY 2012
 SCALE: AS SHOWN

OWN BY: GMK
 DSN BY: GMK/SR
 CKD BY: SR

GENERAL NOTES:
 - CONTOURS SHOWN ARE AT 2 FOOT INTERVALS
 - RED CONTOURS ARE ABOVE PROJECT DEPTH
 - BLUE CONTOURS ARE BELOW PROJECT DEPTH

VOLUSIA COUNTY, FL
 MAINTENANCE DREDGING
 PONCE DE LEON INLET

PLATE:
 07



U.S. Army Corps
of Engineers
Jacksonville District

WQC PLATES
NOT FOR CONSTRUCTION

DEPARTMENT OF THE ARMY
JACKSONVILLE DISTRICT, CORPS OF ENGINEERS
JACKSONVILLE, FLORIDA

FILE NAME:

DATE: FEBRUARY 2012

SCALE: AS SHOWN

DWN BY:
GMK

DSN BY:
GMK/SR

CRD BY:
SR

GENERAL NOTES:


- CONTOURS SHOWN ARE AT 2 FOOT INTERVALS
- RED CONTOURS ARE ABOVE PROJECT DEPTH
- BLUE CONTOURS ARE BELOW PROJECT DEPTH

VOLUSTA COUNTY, FL


**MAINTENANCE DREDGING
PONCE DE LEON INLET**

PLATE:



08



 US Army Corps of Engineers Jacksonville District	WQC PLATES NOT FOR CONSTRUCTION	FILE NAME: DATED: FEBRUARY 2012	DWN BY: GMK DSN BY: GMK/SR CKD BY: SR	GENERAL NOTES: - CONTOURS SHOWN ARE AT 2 FOOT INTERVALS - RED CONTOURS ARE ABOVE PROJECT DEPTH - BLUE CONTOURS ARE BELOW PROJECT DEPTH	VOLUSIA COUNTY, FL MAINTENANCE DREDGING PONCE DE LEON INLET	PLATE: 09
	DEPARTMENT OF THE ARMY JACKSONVILLE DISTRICT, CORPS OF ENGINEERS JACKSONVILLE, FLORIDA	SCALE: AS SHOWN				



 US Army Corps of Engineers Jacksonville District	WQC PLATES NOT FOR CONSTRUCTION	FILE NAME: DATED: SCALE:	DWN BY: GSK DSN BY: GSK/SR CKD BY: SR	GENERAL NOTES: - CONTOURS SHOWN ARE AT 2 FOOT INTERVALS - RED CONTOURS ARE ABOVE PROJECT DEPTH - BLUE CONTOURS ARE BELOW PROJECT DEPTH	VOLUSIA COUNTY, FL MAINTENANCE DREDGING PONCE DE LEON INLET	PLATE: 10
	DEPARTMENT OF THE ARMY JACKSONVILLE DISTRICT, CORPS OF ENGINEERS JACKSONVILLE, FLORIDA	FEBRUARY 2012 AS SHOWN				



WQC PLATES
NOT FOR CONSTRUCTION
 DEPARTMENT OF THE ARMY
 JACKSONVILLE DISTRICT, CORPS OF ENGINEERS
 JACKSONVILLE, FLORIDA


FILE NAME:
 DATED: FEBRUARY 2012
 SCALE: AS SHOWN

DWN BY: GMK
 DSN BY: GMK/SR
 CKD BY: SR

GENERAL NOTES:
 - CONTOURS SHOWN ARE AT 2 FOOT INTERVALS
 - RED CONTOURS ARE ABOVE PROJECT DEPTH
 - BLUE CONTOURS ARE BELOW PROJECT DEPTH

VOLUSIA COUNTY, FL
**MAINTENANCE DREDGING
 PONCE DE LEON INLET**

PLATE:
11



WQC PLATES
NOT FOR CONSTRUCTION
 DEPARTMENT OF THE ARMY
 JACKSONVILLE DISTRICT, CORPS OF ENGINEERS
 JACKSONVILLE, FLORIDA


FILE NAME:
 DATED: FEBRUARY 2012
 SCALE: AS SHOWN

DWN BY: GMK
 DSR BY: GMK/SR
 CKD BY: SR

GENERAL NOTES:
 - CONTOURS SHOWN ARE AT 2 FOOT INTERVALS
 - RED CONTOURS ARE ABOVE PROJECT DEPTH
 - BLUE CONTOURS ARE BELOW PROJECT DEPTH

VOLUSIA COUNTY, FL
**MAINTENANCE DREDGING
 PONCE DE LEON INLET**

PLATE:
12



WQC PLATES
NOT FOR CONSTRUCTION
 DEPARTMENT OF THE ARMY
 JACKSONVILLE DISTRICT, CORPS OF ENGINEERS
 JACKSONVILLE, FLORIDA


FILE NAME:
 DATED: FEBRUARY 2012
 SCALE: AS SHOWN

DWN BY: GMK
 DSN BY: GMK/SR
 CRD BY: SR


GENERAL NOTES:
 - CONTOURS SHOWN ARE AT 2 FOOT INTERVALS
 - RED CONTOURS ARE ABOVE PROJECT DEPTH
 - BLUE CONTOURS ARE BELOW PROJECT DEPTH

VOLUSIA COUNTY, FL
MAINTENANCE DREDGING
PONCE DE LEON INLET



PLATE:
13



 US Army Corps of Engineers Jacksonville District	WQC PLATES NOT FOR CONSTRUCTION	FILE NAME: DATED:	DWN BY: DSN BY: GRD BY:	GENERAL NOTES: - CONTOURS SHOWN ARE AT 2 FOOT INTERVALS - RED CONTOURS ARE ABOVE PROJECT DEPTH - BLUE CONTOURS ARE BELOW PROJECT DEPTH	VOLUSIA COUNTY, FL MAINTENANCE DREDGING PONCE DE LEON INLET	PLATE: 14
	DEPARTMENT OF THE ARMY JACKSONVILLE DISTRICT, CORPS OF ENGINEERS JACKSONVILLE, FLORIDA	FEBRUARY 2012 SCALE: AS SHOWN	GMK GMK/SR SR			



 U.S. Army Corps of Engineers Jacksonville District	WQC PLATES NOT FOR CONSTRUCTION		FILE NAME: _____	DWN BY: GMK	GENERAL NOTES: - CONTOURS SHOWN ARE AT 2 FOOT INTERVALS - RED CONTOURS ARE ABOVE PROJECT DEPTH - BLUE CONTOURS ARE BELOW PROJECT DEPTH	VOLUSIA COUNTY, FL MAINTENANCE DREDGING PONCE DE LEON INLET	PLATE: 15
	DEPARTMENT OF THE ARMY JACKSONVILLE DISTRICT, CORPS OF ENGINEERS JACKSONVILLE, FLORIDA		DATE: FEBRUARY 2012	DSN BY: GMK/SR			
			SCALE: AS SHOWN	CKD BY: SR			



WQC PLATES
NOT FOR CONSTRUCTION

DEPARTMENT OF THE ARMY
JACKSONVILLE DISTRICT, CORPS OF ENGINEERS
JACKSONVILLE, FLORIDA

FILE NAME:

DATED: FEBRUARY 2012

SCALE: AS SHOWN

DWN BY: GMK


BSN BY: GMK/SR

CRD BY: SR


GENERAL NOTES:
- CONTOURS SHOWN ARE AT 2 FOOT INTERVALS
- RED CONTOURS ARE ABOVE PROJECT DEPTH
- BLUE CONTOURS ARE BELOW PROJECT DEPTH

VOLUSIA COUNTY, FL
MAINTENANCE DREDGING
PONCE DE LEON INLET


PLATE:
16



 US Army Corps of Engineers Jacksonville District	WQC PLATES NOT FOR CONSTRUCTION		FILE NAME: DWN BY: GMK	GENERAL NOTES: - CONTOURS SHOWN ARE AT 2 FOOT INTERVALS - RED CONTOURS ARE ABOVE PROJECT DEPTH - BLUE CONTOURS ARE BELOW PROJECT DEPTH	VOLUSIA COUNTY, FL MAINTENANCE DREDGING PONCE DE LEON INLET	PLATE: 17
	DEPARTMENT OF THE ARMY JACKSONVILLE DISTRICT, CORPS OF ENGINEERS JACKSONVILLE, FLORIDA		DATE: FEBRUARY 2012 DSN BY: GMK/SR			
	SCALE: AS SHOWN		CKD BY: SR			



 US Army Corps of Engineers Jacksonville District	WQC PLATES NOT FOR CONSTRUCTION	FILE NAME: DWN BY: GMK	GENERAL NOTES: - CONTOURS SHOWN ARE AT 2 FOOT INTERVALS - RED CONTOURS ARE ABOVE PROJECT DEPTH - BLUE CONTOURS ARE BELOW PROJECT DEPTH	VOLUSIA COUNTY, FL MAINTENANCE DREDGING PONCE DE LEON INLET	PLATE: 18	
	DEPARTMENT OF THE ARMY JACKSONVILLE DISTRICT, CORPS OF ENGINEERS JACKSONVILLE, FLORIDA	DATED: FEBRUARY 2012				DSN BY: GMK/SR
	SCALE: AS SHOWN	CKD BY: SR				



US Army Corps
of Engineers
Jacksonville District

WQC PLATES
NOT FOR CONSTRUCTION

DEPARTMENT OF THE ARMY
JACKSONVILLE DISTRICT, CORPS OF ENGINEERS
JACKSONVILLE, FLORIDA


FILE NAME:
DATED: FEBRUARY 2012
SCALE: AS SHOWN

DWN BY: GMK
DSN BY: GMK/SR
CDD BY: SR


GENERAL NOTES:
- CONTOURS SHOWN ARE AT 2 FOOT INTERVALS
- RED CONTOURS ARE ABOVE PROJECT DEPTH
- BLUE CONTOURS ARE BELOW PROJECT DEPTH

VOLUSIA COUNTY, FL
**MAINTENANCE DREDGING
PONCE DE LEON INLET**

PLATE:
19





A
03
CUT-1A 10+00



B
07
CUT-3N 5+00

PERMIT # 308009001

GRAPHIC SCALE



WQC PLATES
NOT FOR CONSTRUCTION
DEPARTMENT OF THE ARMY
JACKSONVILLE DISTRICT, CORPS OF ENGINEERS
JACKSONVILLE, FLORIDA


FILE NAME:
DATED: FEBRUARY 2012
SCALE: AS SHOWN

DWN BY: GMK
DSN BY: GMK/SR
CKD BY: SR

GENERAL NOTES:


VOLUSIA COUNTY, FL
MAINTENANCE DREDGING
PONCE DE LEON INLET

PLATE:
20



C
07

CUT-5N 4+00



D
13

CUT-12N 5+00

GRAPHIC SCALE

HORIZONTAL 50' 0 50' 100'

VERTICAL 5' 0 5' 10'

PERMIT # 308009001



US Army Corps of Engineers Jacksonville District

WQC PLATES
NOT FOR CONSTRUCTION

DEPARTMENT OF THE ARMY
JACKSONVILLE DISTRICT, CORPS OF ENGINEERS
JACKSONVILLE, FLORIDA

FILE NAME:

DATED:
FEBRUARY 2012

SCALE:
AS SHOWN

DWN BY:
GMK

DSN BY:
GMK/SR

CKD BY:
SR


GENERAL NOTES:

VOLUSIA COUNTY, FL


MAINTENANCE DREDGING
PONCE DE LEON INLET

PLATE:

21




E
16
CUT-2S 10+00



F
18
CUT-3S 18+00

GRAPHIC SCALE



PERMIT # 308009001



US Army Corps of Engineers Jacksonville District

WQC PLATES
NOT FOR CONSTRUCTION

DEPARTMENT OF THE ARMY
JACKSONVILLE DISTRICT, CORPS OF ENGINEERS
JACKSONVILLE, FLORIDA

FILE NAME:

DATED:
FEBRUARY 2012

SCALE:
AS SHOWN

DWN BY:
GMK

DBN BY:
GMK/SR

CRD BY:
SR


GENERAL NOTES:

VOLUSIA COUNTY, FL

**MAINTENANCE DREDGING
PONCE DE LEON INLET**

PLATE:

22



WQC PLATES
 NOT FOR CONSTRUCTION
 DEPARTMENT OF THE ARMY
 JACKSONVILLE DISTRICT, CORPS OF ENGINEERS
 JACKSONVILLE, FLORIDA

FILE NAME:
 DATED: FEBRUARY 2012
 SCALE: AS SHOWN

DWN BY: GMK
 DSN BY: GMK/SR
 CRD BY: SR

GENERAL NOTES:
 - CONTOURS SHOWN ARE AT 2 FOOT INTERVALS
 - RED CONTOURS ARE ABOVE PROJECT DEPTH
 - BLUE CONTOURS ARE BELOW PROJECT DEPTH

VOLUSIA COUNTY, FL
 MAINTENANCE DREDGING
 PONCE DE LEON INLET
 NEARSHORE PLACEMENT AREA

PLATE:
 23